

DAILY MILE

Supplier							
Contact							
Phone							
Quote ref	5 lap option	4 lap option	3 lap option		31402	31402	
Picture							
Preparation of area for new stone sub-base and surfacing	✓	✓	✓	x	n/a	✓	75mm stone base + 25mm stone dust levelled
Supply & installation of geotextile weed suppressing membrane to entirety of circuit	✓	✓	✓	x	✓	✓	x
stone sub-base to entirety of circuit	✓	✓	✓	n/a	n/a	n/a	n/a
Type of Surface	Rhyno Mulch™	Rhyno Mulch™	Rhyno Mulch™	Suds Bond	Resin bound rubber mulch	Resin bound rubber mulch	Artificial Grass
Depth	40mm	40mm	40mm	50mm	40mm	40mm	50mm
Area	385 m2	483 m2	644 m2	500 m2	600 m2	600 m2	650 m2
length	321 m	402 m	536 m	500m	500m	500m	500m
width	1.2M	1.2M	1.2M	1.0 m	1.2 m	1.2 m	1.3 m
Surfacing to be roll-finished into the ground at the edges	✓	✓	✓	cut / ramped into surrounding	not specified	not specified	Wooden tanalised edging
Provisions throughout works to include Heras Security Fencing	✓	✓	✓	?	?	?	?
Leaving site clean and tidy and end of works, removing and disposing of any spoil	✓	✓	✓	✓	✓	✓	?
Cost	£ 30,389.00	£ 36,631.25	£ 46,895.00	£ 30,574.00	£ 33,900.00	£ 69,900.00	£ 32,500.00
VAT	£ 6,077.80	£ 7,326.25	£ 9,379.00	£ 6,114.80	£ 6,780.00	£ 13,980.00	£ 6,500.00
TOTAL	£ 36,466.80	£ 43,957.50	£ 56,274.00	£ 36,688.80	£ 40,680.00	£ 83,880.00	£ 39,000.00