

Estimate for hard standing area at bus stops

To provide labour and materials to construct two hard standing areas at the bus stops in Lynn Road, near the entrance to Highfield Avenue. To remove all vegetation, reduce dig to a depth of 300mm and remove all spoil from site. Lay, level and compact type 1 hardcore or similar to an approximate depth of 230mm, lay 12 x 600mm x 600mm x 50mm slabs on a solid sand and cement bed, for each bus stop.

Estimate price £ 2050.00 + VAT

The estimate shown above, includes the hire and installation of temporary traffic lights from a traffic management company. This is for the out of town side only, where there is limited space available for the construction works to take place.

Please note.

I have contacted Highways asking for their bus stop specification, but have had no reply so far. I am aware there should be disabled access to the buses and looking at other stops within the town, higher road kerbs have been installed, along with the textured slabs for visually impaired people. Neither of these items have been allowed for because no dimensions or quantities are known.