

SCHEDULE E SOFTWORKS

Item	Description	Quantity	Unit	Rate	Total
				£/p	£/p
1	<u>Topsoiling</u>				
a	Lift topsoil from stockpile on site, pass through 6mm screen and remove debris in preparation for re-use on site.	425	m ³		
b	Spread topsoil stored on site to a depth of 100mm for areas to be seeded, (grass reinstatement areas)	780	m ²		
2	<u>Grass grid seeding</u>				
a	Supply and lay 100mm depth rootzone sand soil mix in grass grid paving	190	m ²		
b	Supply and sow amenity grass seed to grass grid areas at rate of 35g/m2.	190	m ²		
3	<u>Grass seeding to areas to be made good</u>				
a	Reinstate existing grass disturbed during the work on completion by seeding with amenity grass seed.	780	m ²		
Total carried forward to Summary Page					